

**INDIAN INSTITUTE OF TOURISM AND TRAVEL MANAGEMENT**

**LIMITED TENDER NOTICE**

**For carrying out various minor works, undertaking fabrication works and supplies etc.  
at National Institute of Water Sports, Goa ( a center of IITTM)**

**The limited tender are hereby invited for the following minor works, undertaking fabrication works and to arrange supplies of various items at National Institute of Water Sports, Goa (a center of IITTM) latest by 16.03.2023 (upto 3.00 pm) at the address given below in sealed cover by speed post/by hand to dropped in the tender box placed at the reception counter of Indian Institute of Tourism and Travel Management, Govindpuri, Gwalior-474 011 (MP):-**

1. Carrying out minor civil works as detailed in the annexure attached.
2. Carrying out of minor Civil works for water supply and sanitation works as per details provided in the annexure attached.
3. Supply of planters with plants, manure and plants medicines as per details provided in the annexure attached.
4. Hiring of lighting services, Chairs, Tents, setting up of stage, carpets, chandeliers, sofas, tables, audio system, speakers, fans etc. as per the details provided in the annexure attached.
5. Fabrication of iron entrance as well as main gates as per the details and specifications mentioned in the annexure attached.

**Terms and conditions:**

1. The minor works to be carried out will be based on each item rate to be quoted by the tenderer.
2. The rates to be quoted for the works and supplies shall be all inclusive. The taxes payable should not be mentioned separately by the tenderer in the quote.
3. The items to be supplied and works to be carried out will be at the consignee's place.
4. No cartage will be paid for bringing the items to be brought at the NIWS, Goa site and the supply to be made.
5. The responsibility for supplying the items at NIWS, Goa and works to be carried out in good condition shall lie on the successful bidder.
6. The delay in carrying out the works and undertaking of supplies shall attract the penalty clause of 1% of the total cost per day.
7. The quality of works and the supply made by the successful bidder will not be compromised in any case.
8. All the disputes between IITTM and the successful bidders shall be subject to the jurisdiction of courts at Gwalior
9. The envelope for each bid should be **super scribed-Bids for supplies/works to be undertaken at NIWS Goa.**

**Address on which the limited tenders are to be submitted**

**The Director,  
Indian Institute of Tourism and Travel Management  
Govindpuri, Gwalior-474 011 (MP)**

\*\*\*\*

## Indian Institute of Tourism and Travel Management

### Limited Tender for Carrying out minor civil works as detailed

#### ANNEXURE - I

S.No.	DSR Ref.	Particulars of item	No.	QUANTITY	Unit	Rates	Amount	Remarks
1	2.6.1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. 2.6.1 All kinds of soil						
		<b>Total</b>		<b>2500</b>	<b>Cum</b>			
2	2.25	2.25 Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.						
		<b>Total</b>		<b>77</b>	<b>Cum</b>			
3	2.25a	2.25(a) Excavating, supplying and filling of local earth (including royalty) by mechanical transport upto a lead of 5km also including ramming and watering of the earth in layers not exceeding 20 cm in trenches, plinth, sides of foundation etc. complete.						
		<b>Total</b>		<b>12</b>	<b>Cum</b>			
4	2.31	2.31 Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth up to 30 cm measured at a height of 1 m above ground level and removal of rubbish up to a distance of 50 m outside the periphery of the area cleared.						
		<b>Total</b>		<b>14000</b>	<b>Sqm</b>			
5	4.1.5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:3:6 (1 Cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources)						
		<b>Total</b>		<b>4.67</b>	<b>Cum</b>			

6	5.1.2	1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived						
		<b>Total</b>		2.1	Cum			
7	5.3	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)						
		<b>Total</b>		3.2	Cum			
8	5.22A.6	Steel reinforcement for R.C.C. work including						
		<b>Total</b>		111	kg			
9	6.1.	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in:1 Cement mortar 1:4 (1 cement : 4 coarse sand)						
		<b>Total</b>		17	Cum			
10	7.32	Stone work, plain in copings, cornices, string courses and plinth courses, upto 75 mm thick in Cement mortar 1:6 (1 cement : 6 coarse sand), including pointing with white cement mortar 1:2 (1 white cement : 2 stone dust) with an admixture of pigment matching the stone shade. Red sand stone cum						
		<b>Total</b>		0.52	Cum			
				<b>Grand Total</b>				
		<b>Note</b> : Payment shall be made as per actual work done.						

## Indian Institute of Tourism and Travel Management

### Limited tender for Carrying out of minor Civil works for water supply and sanitation works

#### ANNEXURE - II

S.No.	DSR Ref.	Particulars of item	QUANTITY	Unit	Rates	Amount	Remarks
1	2.6.1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-incharge. 2.6.1 All kinds of soil					
		<b>Total</b>	42	Cum			
2		Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge.					
3	18.9.5	40 mm nominal dia Pipes metre 559.20					
		<b>Total</b>	225	metre			
4	19.6	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete					
5	19.6.1	100 mm dia. R.C.C. pipe					
		<b>Total</b>	205	metre			
6	19.6.2	150 mm dia. R.C.C. pipe					
		<b>Total</b>	147	metre			
7	19.6.3	250 mm dia. R.C.C. pipe					
		<b>Total</b>	63	metre			
8	19.36	Providing and laying Non Pressure NP-4 class (Heavy duty) R.C.C. pipes including collars/spigot jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete					
9	19.36.2	600 mm dia RCC pipes.					
		<b>Total</b>	30	metre			

10	16.68	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge.					
		<b>Total</b>	108	Sqm			
				Grand Total			
		<b>Note :</b> Payment shall be made as per actual work done.					



**INDIAN INSTITUTE OF TOURISM AND TRAVEL MANAGMENT**

**Limited Tender for hiring of lighting services, Chairs, Tents, setting up of stage, carpets, chandeliers, sofas, tables, audio system, speakers, fans etc.**

**Annexure-IV**

S. No.	Item/Particular	Qty	Size/Quantity (Per Day)	Rate (Rs.)	Amount (Rs.)
1	Table with table cloth & Frill	5 No.	Each		
2	VIP Chair	10 No.	Each		
3	New cloth Chandani	As per Req.	Sq. Ft.		
4	New cloth Ceiling	As per Req.	Sq. Ft.		
5	Fixed Stage on board	600 Sq Ft.	Sq. Ft.		
6	Water proof pandal	3000 Sq Ft	Sq. Ft.		
7	TRASS with ceiling	As per Req.	Sq. Ft.		
8	New Green Carpet	As per Req.	Sq. Ft.		
9	Mineral Water Glass (250gm)	500 No.	Each		
10	Complete Bedding	As per Req.	Each		
11	Fan Pad	50	Each		
12	VIP Sofa Set (2 seater)	10 No.	Each		
13	Gole Takiya with cover	40 No.	Each		
14	Center Table (Glass) with cover	10 No.	Each		
15	Mineral Water Bottle (250gm)	500 No.	Each		
16	Plastic Chair	300 No.	Each		
17	Dari	N/A	Each		
18	Mineral Water (20 Ltrs.)	20 No.	Each		
19	Dispenser	10 No.	Each		
20	Mist Fan	10 No.	Each		
21	Conference Table with frill	N/A	Each		
22	Disposable Glass (Mineral water)	1000 No.	Each		
23	Revolving Arm Chair	4 No.	Each		
24	LED Screen on back of stage	1	Each		
25	New white side wall	As per Req.	Sq. Ft.		
26	Dunlope Gadda	N/A	Each		
27	Stage Cordless Mic	3	Each		
28	Speakers	6 Pair	Each		
29	LED Lights	As per requirement	Each		
30	LED Spot Light	As per requirement	Each		
31	Generator Soundless	4	Each		
32	Chandeliers	As per requirement	Each		
				<b>Gross Total (Rs.)</b>	

**Indian Institute of Tourism and Travel Management**  
**Limited Tender For Fabrication of iron entrance as well as main gates**  
**as per the details and specifications given below**

**ANNEXURE - V**

S.No.	DSR Ref.	Particulars of item	No.	QUANTITY	Unit	Rates	Amount	Remarks
1	2.6.1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. 2.6.1 All kinds of soil						
		<b>Total</b>		3	Cum			
2		Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge.						
3	18.9.5	40 mm nominal dia Pipes metre 559.20						
		<b>Total</b>		195	metre			
4	19.6.1	19.6 Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete						
5	19.6.1	100 mm dia. R.C.C. pipe						
		<b>Total</b>		98	metre			
6	19.6.2	150 mm dia. R.C.C. pipe						
		<b>Total</b>		39	metre			
7	19.6.3	250 mm dia. R.C.C. pipe						
		<b>Total</b>		18	metre			
8	19.36	Providing and laying Non Pressure NP-4 class (Heavy duty) R.C.C. pipes including collars/spigot jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete metre 2720.00						
9	19.36.1	450 mm dia RCC pipes.						
		<b>Total</b>		15	metre			



10	10.16	10.16 Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. kg 168.95					
11	10.16.2	Hot finished seamless type tubes					
		<b>Total</b>	3150	Kg			
12	NDSR	Providing and fixing of 40 mm dia GI pipe for flags in the ground complete in all respect excluding cost of flags.(6 meters high from GL)					
		<b>Total</b>	120	meter			
13	10.25	10.25 Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. including use of chequered plate wherever required, all complete 10.25.2 kg 142.30					
14	10.25.2	In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works					
		<b>Total</b>	850	Kg			
15	4.1.5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:3:6 (1 Cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources)					
		<b>Total</b>	1	Cum			
16	6.1.	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: 1 Cement mortar 1:4 (1 cement : 4 coarse sand)					
		<b>Total</b>	6	Cum			
					<b>Grand Total</b>		
		<b>Note :</b> Payment shall be made as per actual work done.					